


Name of the work: Supply, Installation, Testing & Commissioning of Gel earthing for Modular Operation Theatres at AIIMS, Jodhpur.

N.I.T. No.: AIIMS-JDH/EE/ELECT/2019-20/01

CORRIGENDUM / ADDEMDUM

S. No.	Ref. Page No. of Document	Existing	To be read as-
1.	Financial bid & Page No. 48 / 53 of TED	<p><u>Item no. 2.</u></p> <p>Supplying and laying 50mm X 6mm copper strip at 0.50 meter below ground as strip earth electrode, including connection/ terminating, making hole and making good as it is with nut, bolt, spring, washer etc. as required. (Joining shall be done by overlapping and with 2 sets of BRASS NUT BOLT & spring washer spaced at 50mm)</p>	<p><u>Item no. 2.</u></p> <p>Supplying and laying 50mm X 6mm copper strip at 0.50 meter below ground / on surface / on wall mounted as strip earth electrode, including connection/ terminating, making hole and making good as it is with nut, bolt, spring, washer etc. as required. (Joining shall be done by overlapping and with 2 sets of BRASS NUT BOLT & spring washer spaced at 50mm)</p>
1.		<p><u>Item no. 3.</u></p> <p>Supplying and laying 50mm X 6mm copper strip at 0.50 meter below ground as strip earth electrode, including connection/ terminating, making hole and making good as it is with nut, bolt, spring, washer etc. as required. (Joining shall be done by overlapping and with 2 sets of BRASS NUT BOLT & spring washer spaced at 50mm)</p>	<p><u>Item no. 3.</u></p> <p>Supplying and laying 25mm X 5mm copper strip at 0.50 meter below ground / on surface / on ceiling as strip earth electrode, including connection/ terminating, making hole and making good as it is with nut, bolt, spring, washer etc. as required. (Joining shall be done by overlapping and with 2 sets of BRASS NUT BOLT & spring washer spaced at 50mm)</p>


(Er. Pankaj Saxena)
Executive Engineer (Electrical)
AIIMS, Jodhpur